

Pavement Design Report

Project	Kestrel Valley Link Road
Document	KVL-ADM-200-RP-C-0017
Revision	P02
Status	AP - For approval
Date	6 December 2024
Originator	Arden Moss Consulting Engineers

Rev	Date	Description
P01	20/09/2024	Issued for review
P02	06/12/2024	Updated subgrade assessment - submitted for approval

1 Scope

This revision updates the subgrade assessment for the mainline carriageway. Junction layouts remain outside its scope.

2 Design traffic

Design traffic is unchanged at 12 million standard axles.

3 Pavement construction

Layer	Material	Thickness (mm)
Surface course	SMA 10, PSV 68 aggregate	40
Binder course	AC 20 dense binder	60
Base	AC 32 dense base	150
Subbase	Type 1 unbound mixture	225

4 Foundation

Capping of 350 mm Class 6F2 is required between Ch 1+600 and Ch 2+200, where the subgrade CBR is 3 per cent. Elsewhere 150 mm of capping is sufficient.

Prepared by: Nadia Hussain, Highways Engineer, Arden Moss Consulting Engineers