

Earthworks Compaction Test Report - August 2025

Project	Kestrel Valley Link Road
Document	KVL-CGC-200-RP-C-0023
Revision	P01
Status	FI - For information
Date	5 September 2025
Originator	Castlegate Civils Ltd

Rev	Date	Description
P01	05/09/2025	Issued

1 Summary

Compaction testing of embankment fill and capping in August 2025. All results meet the specification. Earthworks cut is substantially complete.

2 Results

Chainage	Layer	Relative compaction (%)	Result
3+120	Fill layer 5	96.30	Pass
3+480	Capping	97.80	Pass
3+900	Fill layer 2	95.40	Pass

Prepared by: Lee Hartley, Quality Manager, Castlegate Civils Ltd