


SECTION THROUGH MILL LANE CULVERT



Box culvert 3.0 m x 2.0 m internal

— Road level +14.60 mAOD

— 300 mm water main invert +13.40 mAOD

— Culvert roof +12.65 mAOD

— Culvert invert +10.35 mAOD

NOTES

- 1. Invert lowered from +10.80 to +10.35 mAOD following RFI-0013. Roof slab top +12.65 mAOD.
- 2. Existing water main at +13.40 mAOD (trial holes TH1 to TH3). Clearance 0.75 m.
- 3. Water main protection slab to KVL-ADM-330-DR-S-0206.

Rev	Date	Description
C02	20/08/2025	Invert lowered 450 mm following RFI-0013
C01	05/03/2025	Issued for construction
P01	20/11/2024	Issued for review

Client: Northvale County Council
Designer: Arden Moss Consulting Engineers
Kestrel Valley Link Road
Mill Lane Culvert General Arrangement
Drawing number: KVL-ADM-330-DR-S-0205
Revision: C02 Status: FC - For construction
Scale: 1:50 @ A1 Date: 20 August 2025
Drawn: LC Checked: PN Approved: DO