

# River Kest Bridge Deck Concrete Trial Mix Report

|            |                          |
|------------|--------------------------|
| Project    | Kestrel Valley Link Road |
| Document   | KVL-CGC-410-RP-S-0024    |
| Revision   | P01                      |
| Status     | FI - For information     |
| Date       | 22 April 2025            |
| Originator | Castlegate Civils Ltd    |

| Rev | Date       | Description |
|-----|------------|-------------|
| P01 | 22/04/2025 | Issued      |

## 1 Purpose

Trial mixes for the C40/50 deck slab concrete, to confirm workability, strength development and pumpability before the deck pours.

## 2 Results

| Mix | Slump (mm) | 7-day strength (N/mm2) | 28-day strength (N/mm2) |
|-----|------------|------------------------|-------------------------|
| TM1 | 120        | 34.50                  | 52.00                   |
| TM2 | 150        | 33.00                  | 50.50                   |

## 3 Recommendation

Mix TM1 is proposed for the deck slab pours.

Prepared by: Lee Hartley, Quality Manager, Castlegate Civils Ltd