

Pavement Design Report

Project	Kestrel Valley Link Road
Document	KVL-ADM-200-RP-C-0017
Revision	P01
Status	RV - For review and comment
Date	20 September 2024
Originator	Arden Moss Consulting Engineers

Rev	Date	Description
P01	20/09/2024	Issued for review

1 Scope

This report sets out the pavement construction for the Kestrel Valley Link Road mainline carriageway. It does not cover junction layouts, which are designed separately.

2 Design traffic

Design traffic is 12 million standard axles over a 40-year design life, based on the council's traffic forecast for the opening year.

3 Pavement construction

Layer	Material	Thickness (mm)
Surface course	SMA 10, PSV 68 aggregate	40
Binder course	AC 20 dense binder	60
Base	AC 32 dense base	150
Subbase	Type 1 unbound mixture	225

4 Foundation

A capping layer of Class 6F2 material is required where the subgrade CBR is below 5 per cent. Capping thickness is set per cutting from the earthworks testing.

Prepared by: Nadia Hussain, Highways Engineer, Arden Moss Consulting Engineers