

Drainage Strategy Report

Project	Kestrel Valley Link Road
Document	KVL-ADM-300-RP-D-0014
Revision	P01
Status	RV - For review and comment
Date	14 June 2024
Originator	Arden Moss Consulting Engineers

Rev	Date	Description
P01	14/06/2024	Issued for review

1 Introduction

This report sets out the surface water drainage strategy for the Kestrel Valley Link Road. Runoff from the new carriageway is collected by kerb drainage and carrier drains and attenuated in two ponds before discharge.

2 Attenuation ponds

Pond 1 West serves chainage 0+000 to 2+100 and discharges to the Kest tributary. Pond 2 East serves chainage 2+100 to 4+200 and discharges to Mill Brook upstream of the Mill Lane culvert.

Pond	Catchment (ha)	Storage (m3)	Discharge limit (l/s)
Pond 1 West	4.10	1650	6.00
Pond 2 East	5.30	2150	8.00

3 Discharge limits

Discharge limits are set at the greenfield runoff rate for the 1 in 1 year event, as agreed in principle with Northvale County Council as lead local flood authority.

Prepared by: Sam Whitfield, Drainage Engineer, Arden Moss Consulting Engineers