

Eastern Roundabout Road Safety Audit Response

Project	Kestrel Valley Link Road
Document	KVL-ADM-510-RP-C-0019
Revision	P01
Status	FI - For information
Date	10 February 2025
Originator	Arden Moss Consulting Engineers

Rev	Date	Description
P01	10/02/2025	First issue

1 Introduction

The designer's response to the stage 2 road safety audit of the Eastern Roundabout detailed design.

2 Audit problems and responses

Problem	Audit comment	Designer response
2.1	Forward visibility on the north arm limited by planting	Planting set back 3 m
2.2	Uncontrolled crossing on the east arm too close to the give-way line	Crossing moved 5 m back
2.3	Skid resistance on the approaches	Adequate - PSV 68 surface course specified on all arms

Prepared by: Nadia Hussain, Highways Engineer, Arden Moss Consulting Engineers