

Drainage Strategy and Attenuation Design Report

Project	Kestrel Valley Link Road
Document	KVL-ADM-300-RP-D-0021
Revision	P01
Status	AP - For approval
Date	30 July 2025
Originator	Arden Moss Consulting Engineers

Rev	Date	Description
P01	30/07/2025	Submitted for approval - supersedes KVL-ADM-300-RP-D-0014

1 Introduction

This report supersedes the Drainage Strategy Report KVL-ADM-300-RP-D-0014. It responds to Northvale County Council's letter KVL-NCC-320-LT-D-0011, which reduced the Pond 2 East discharge limit from 8.0 l/s to 5.0 l/s.

2 Attenuation design

To meet the 5.0 l/s limit, Pond 2 East storage increases from 2,150 m³ to 2,780 m³. The pond base is lowered from +10.60 mAOD to +10.20 mAOD and the footprint extended north by 8 m. Pond 1 West is unchanged.

Pond	Catchment (ha)	Storage (m ³)	Discharge limit (l/s)
Pond 1 West	4.10	1650	6.00
Pond 2 East	5.30	2780	5.00

3 Flow control

The Pond 2 East flow control device must pass no more than 5.0 l/s at the design head of 1.8 m. Revised drawings KVL-ADM-320-DR-D-0320 and KVL-ADM-300-DR-D-0303 will be issued at revision C02.

Prepared by: Sam Whitfield, Drainage Engineer, Arden Moss Consulting Engineers