

Drainage Strategy Report

Project	Kestrel Valley Link Road
Document	KVL-ADM-300-RP-D-0014
Revision	P02
Status	AP - For approval
Date	29 November 2024
Originator	Arden Moss Consulting Engineers

Rev	Date	Description
P01	14/06/2024	Issued for review
P02	29/11/2024	Detailed design update - submitted for approval

1 Introduction

This revision updates the drainage strategy for detailed design. Catchment areas and pond volumes are confirmed from the detailed highway model.

2 Attenuation ponds

Pond 1 West and Pond 2 East are retained as at revision P01. Each pond has a vortex flow control chamber at its outlet.

Pond	Catchment (ha)	Storage (m3)	Discharge limit (l/s)
Pond 1 West	4.10	1650	6.00
Pond 2 East	5.30	2150	8.00

3 Discharge limits

Discharge limits remain at the greenfield runoff rate. Any change to the flood model for Mill Brook may require the Pond 2 East limit to be revisited.

Prepared by: Sam Whitfield, Drainage Engineer, Arden Moss Consulting Engineers